



# ***CNS CONFERENCE***

## ***Qinshan Project - June 2003***

***Dr. Ken Petrunik***



Canada 



# **CANDU CONSTRUCTION IN CHINA**

## **Ahead of Schedule – Under Budget**





# ***Contents***

**Reference Data**

**Participants**

**Challenges**

**How We Did It**

**Qinshan Phase 3 – Project Management; Quality;  
Construction Methods; Integrated Schedules; World  
Records**

**Conclusions**

**Q3R**



**Qinshan CANDU Site (Haiyan)**

**Site - Detailed Location in China**



# ***Reference Data***

- **Qinshan III CANDU NPP**
  - 2 x 728 MWe by AECL and TQNPC
  - Zhejiang Province, China
- **Contract effective – 1997 Feb 12**
- **Start construction – 1998 Jun 8**
- **Scheduled in-service:**
  - Unit 1: 2003 Feb 12 – **Actual 2002 Dec 31**
  - Unit 2: 2003 Nov 12- Predicted 2003 July



**October 1997**





# Major Participants

- **AECL overall project manager, designs & supplies NSP, manages NSP construction**
- **Third Qinshan Nuclear Power Company (TQNPC) owner, manages BOP construction & executes commissioning**
- **Chinese Construction Contractors CNI-23, HXCC, CNI-22, ZTPC**
- **Consortium of Hitachi/Bechtel for BOP design and supply**



# Contract Structure

	NSP		BOP
<b>Project Management</b>	<b>AECL</b>		
<b>Engineering Design</b>	<b><u>NSSS Design</u></b> AECL	<b><u>BNSP Design</u></b> <b>CANATOM NPM</b> BNSP Subcontract	<b>BOP Consortium</b> Design & Supply Subcontract
<b>Supply</b>	<b>CANATOM NPM</b> NSP Supply Subcontract		<b>BOP Consortium</b> Design & Supply Subcontract
	<b>Hitachi</b> NSP Supply Subcontract		
	<b>HANJUNG</b> NSP Supply Subcontract		
<b>Site Construction Management</b>	<b>CANATOM NPM</b> Project Management Subcontract		<b>TQNPC</b>
<b>Commissioning</b>	<b>TQNPC under guidance and direction by AECL</b>		
<b>Construction</b>	<b>NSP Construction Contractors</b> (under AECL direction)		<b>BOP Construction Contractors</b> (under TQNPC direction)
<b>Training</b>	<b>Hydro Quebec</b> NSP Training Subcontract		<b>BOP Consortium</b> Design & Supply Subcontract
<b>Heavy Water and Fuel</b>	<b>AECL</b>		





# CHALLENGES


- **Many participants-not worked together before on a project**
- **Unfamiliarity with China**
- **Shortest schedule of any NPP committed in China**
- **First CANDU in China**
- **Regionalized construction not able to benefit from prior PWR experience**
- **Smallest site in China with water on three sides**
- **Internal focus on jobs in government companies, not on best for task - structural steel had large schedule impact**



- **Chinese planning milestone based**
- **Different country and company cultures – AECL – Chinese – Bechtel - Hitachi**
- **Young inexperienced Chinese commissioning staff**
- **Complex execution model; owner manages BOP construction, AECL directs NSP contractors - owner pays**
- **CONTRACT- LUMP SUM with LDs**
- **AECL first time use of CADDs, Open Top and all electronic document systems---”on the run”**
- **Needed to take site construction quality from a paper to effective program.**



# HOW WE DID IT



# TEAMWORK







## **Meeting the Schedule – Qinshan Phase III**

- **Good people and teamwork among participants**
- **Project management leadership and culture with good support from head office and freedom to do job within context of total Contract – focal point accountability**
- **Good client (TQNPC) and local construction contractors**
- **State of the Art Project Management Tools**
- **Early planning, integrated schedules and parallel activities**
- **Improved construction methods-open top**



- **Large part of design ready at CED for NSP**
- **Team in place at CED to produce all project procedures at Rev 0 before work started.**
- **Design by area not system to match actual construction program**
- **Effective training and support from Hydro Quebec Gentilly 2 CANDU 6 station**
- **Excellent commissioning by integrated Chinese and Canadian Teams**

**NOTE: PROJECT decisions on CADDs, open top, electronic tools made after Contract signing based on dealing with RISKS and CHALLENGES**





# Quality a Priority

- Promoted NCR culture
- Used NCRs to control and stop work on a localized area
- Used stop work orders to set policy and direction
- Electronic document system supported quality records and processes
- “All” expat site staff were quality surveyors
- Quality was a LINE responsibility
- Client and contractors evolved to accepting International Quality Program-cultural shift
- Independent Chinese QS body on NSP program



## ***State of the Art Project Management Tools***

- **CADDs – LESS errors and better understanding of overall design and equipment to support easier installation – MANY interferences eliminated**
- **CANDU Material Management System (CMMS)**
  - tracks equipment and materials from RFQ to issue for construction
  - system supports ongoing plant operation & maintenance
  - items bar coded for inventory control and reduced costs



# ***State of the Art Project Management Tools (contd.)***

- **Asset Information Management (AIM) - all “formal” project records in electronic format**
  - on-line and common access to official drawings and documents by all parties
  - reduces errors
  - real time access by all parties
    - dramatically improves quality & efficiency
    - reduces costs
- **IntEC – Integrated database for wiring/cabling and Instrument calibration with real time access.**



# **Construction Methods**

- Modularization & VHL (Open Top)**
  - Shortens installation time
  - Work access from top and bottom
  - Reduces construction labor and interferences between contractors
  - Gives schedule flexibility
  - Done on site for Qinshan after Contract signed
  - Improves quality
  - **REDUCES COSTS**
  - Compensated for other project delays



# ***Integrated Schedules***

- **76 event contract milestone schedule**
- **8500 event level 2 schedule shows**
  - **design deliverables**
  - **equipment deliveries**
  - **construction & commissioning activities**
- **Integrated level 3 schedule by construction contractors**
- **Parallel activities between civil and installation**
  - **New for Chinese but shortened schedule**

**1998 SEPTEMBER**





**OCTOBER 1998**





**OCTOBER 1998**





**NOVEMBER 1998**



Coffer Dam



**DECEMBER 1998**





January 1999





**JANUARY 1999**





March 1999





**MARCH 1999**





**March 1999**









## **Major Lifts (tons) - (70 lifts done)**

- **Steam generator - 220**
- **Temporary roof - 150**
- **Pressurizer - 103**
- **Reactivity deck - 43**
- **Feeder frames - 40 each,**
- **Condenser shells - 270 each,**
- **T/G stator - 280**



- **Evolution of Reference Plant design by Chinese contractors and AECL for modularization of:**
  - dousing steel and piping
  - lower dome formwork
  - spent fuel transfer
- **AECL staffing featured hands on field staff to provide training for contractors. Unit 2 durations about 3/4 of Unit 1**



July 1999  
Condenser Heavy Lift Unit 1



**December 1999**



**November 2000**  
**Dousing Module Lift**





April 2001





January 2003







# ***Commissioning TEAM***

- **TQNPC - 1000 staff**
- **AECL, Bechtel and Hitachi - 46 expat advisors**
- **232 TQNPC staff trained at Gentilly 2 NPP in Canada**
- **Full scope CANDU 6 simulator on-site**
- **Control room operators licensed by NNSA**
- **Integrated team very successful**

October 2001





## ***World Records by Chinese Nuclear Contractors CNI 23 and HXCC***

- **Slipforming Unit 1** 18 days
- **Slipforming Unit 2** 14 days
- **FC installation Unit 1** 69 days
- **FC installation Unit 2** 64 days
- **Steam generator installation** 8 hours
- **Pressurizer installation** 8 hours



# ***New Record for Chinese NPP Construction***

	<b>First Concrete to Criticality (Months)</b>	<b>Criticality (Year)</b>	<b>First Concrete to 100% Power</b>
<b>Qinshan I</b>	<b>77</b>	<b>1991</b>	<b>87</b>
<b>Qinshan II (U 1)</b>	<b>66</b>	<b>2001</b>	<b>70</b>
<b>Daya Bay U1</b>	<b>71.5</b>	<b>1993</b>	<b>75.5</b>
<b>Daya Bay U2</b>	<b>69.5</b>	<b>1994</b>	<b>71.5</b>
<b>Ling'ao U1</b>	<b>56.5</b>	<b>2002</b>	<b>60.5</b>
<b>Ling'ao U2</b>	<b>55.5</b>	<b>2002</b>	<b>57.5</b>
<b>Qinshan III (U 1)</b>	<b>51.5</b>	<b>2002</b>	<b>54</b>



# Qinshan Early Completion

Plant	Q3 earlier by months from CED
Daya Bay 1 FRAMATOM	17
Daya Bay 2 FRAMATOM	13
Qinshan II-1 CNNC	16
Qinshan II-2* CNNC	>20
Ling'ao 1 Guangdong	6
Ling'ao 2 Guangdong	6
Qinshan III-1 AECL	0
Qinshan III-2* AECL	0
Tianwan 1* MINATOM	13
Tianwan 2* MINATOM	18

\*predicted





## ***June 2003***

- **Owner's staff: 900**
- **Contractors direct site labour force: 500 (down from 8000 peak)**
- **AECL & offshore subcontractors: 60 expatriates on site (peak of 180)**
- **Unit 2 Criticality April 29, 2003**
- **On Track to Full Power in summer 2003 – months ahead of schedule**



# Summary and Conclusions

- **AECL CANDU 6 built to shortest construction schedule of any NPP in China even though it was first CANDU**
- **Experience and achievements of Chinese contractors and owners commissioning group show that with earlier design and procurement, and some added modularization, construction of the CANDU 6 which is an existing design and proven technology, can be shortened to give a 66 month project schedule from CED. NOTE: Much better possible for NEW design (ACR) which integrates design and construction and commissioning during design phase.**

# HOW WE DID IT PROJECT MANAGEMENT AND TEAMWORK







# CANDU Q3R

- **Replicate Qinshan III**
- **Same design except pump house**
- **China as project manager**
- **Same Chinese contractors**
- **AECL with Hitachi and Bechtel provide equipment and technical support**
- **Increased localization**
- **China does commissioning**




## **CANDU Q3R (CONTD.)**

- **Cost about  $\frac{1}{4}$  less than Q III (1500\$ kw)**
- **Schedule 66 months vs. 72 months for QIII**
- **Shortest schedule in China supports faster connection to grid.**



# *The last 20 years: 7% p.a. growth China's Electricity Generation*








# The next 50 years – 3.5% p.a. growth

## China: Total Generating Capacity





# ***Nuclear Potential in China***

## **Generating Capacity Additions**

	<b>Short Term 2003-2015</b>	<b>Long Term 2003-2050</b>
<b>Total capacity added, MW/yr</b>	<b>30,000</b>	<b>36,000</b>
<b>Nuclear market share</b>	<b>6%</b>	<b>16%</b>
<b>Nuclear capacity added, MW/yr</b>	<b>1,800</b>	<b>6,000</b>



## **CANDU Opportunities in China**

- **CANDU advantage is short schedule, economic, fuel cycle flexibility**
- **Ongoing good performance of Qinshan supporting new projects**
- **Good Chinese Canadian partnership**







# AECL